

Queen's
UNIVERSITY



CIPANP 2015

Commissioning the DEAP3600 Detector


Dr Mark Ward
Queen's University, Canada

On Behalf of the DEAP
Collaboration

DEAP3600 Collaboration



Carleton
UNIVERSITY



TRIUMF  **SNOLAB**
MINING FOR KNOWLEDGE
CREUSER POUR TROUVER... L'EXCELLENCE

US
University of Sussex



Science & Technology
Facilities Council



Laurentian University
Université **Laurentienne**


DEAP3600

- ❖ Single phase liquid argon (LAr) dark matter detector
- ❖ Located at SNOLAB, 2070m underground in Vale's Creighton mine, Sudbury Ontario, Canada




DEAP3600

- ❖ 3600 kg liquid argon target
 - ❖ 1000 kg fiducial
- ❖ Acrylic vessel
 - ❖ Ultra high purity acrylic
 - ❖ Resurfaced in-situ
- ❖ Vacuum deposited Tetraphenyl butadiene (TPB) wavelength shifter
- ❖ 255 PMTs
 - ❖ Mounted on 20 inch light guides
- ❖ Shielding
 - ❖ Acrylic light guides and high density polyethylene filler material
 - ❖ Water shield tank



Liquid Argon Scintillation






- ❖ Ionization of ultra high purity argon allows the production of excited dimers
- ❖ Formation of singlet and triplet states which have well separated lifetimes (7ns versus 1.5 μ s)
- ❖ Ratio of singlet and triplet states are exploited to produce excellent pulse shape discrimination (PSD)
- ❖ Radiative decay produces 128 nm light
- ❖ Projected light yield of 8 pe/keV_{ee}

Pulse Shape Discrimination

- ❖ Electronic and nuclear recoils produce different ratios of singlet and triplet states.

DEAP-1



$$F_{\text{prompt}} = \frac{N_{\text{prompt}}}{N_{\text{total}}}$$

DEAP-1 Data

arXiv:0904.2930

Backgrounds

Budget for 3 year run <0.6 events


Background	Raw No. Events in Energy ROI	Fiducial No. Events in Energy ROI
Neutrons	30	<0.2
Surface α	150	<0.2
^{39}Ar β (natural)	1.6×10^9	<0.2
^{39}Ar β (depleted)*	8.0×10^7	<0.01

* Factor of 20 reduction
 - Possible factor of 100

Energy ROI : 60 - 120 KeVr

- ❖ Neutron recoils : (α, n) fission and μ -induced
 - ❖ Controlled by strict material screening and assay
 - ❖ Shielding (Acrylic + HDPE + Water)
- ❖ Surfaces : Rn daughters and contamination
 - ❖ Resurfacing acrylic vessel to reach bulk background levels
 - ❖ Passivation of all argon wetted surfaces
 - ❖ Fiducialisation
- ❖ β/γ events : ^{39}Ar
 - ❖ 1 Bq/kg
 - ❖ Predicted PSD reduction > 10^{-10}


AV alpha background reduction





❖ Acrylic ²¹⁰Pb purity < 1.1x10⁻¹⁹ g/g - 0.1 events/3 years

DEAP3600 Resurfacer


- ❖ Designed for 0.1-1mm acrylic removal inner AV
- ❖ Radon scrubbed N₂ purge gas and UPW controls Rn levels during operation.
- ❖ Surface contamination reduced to bulk purity levels
- ❖ Deployed September 2014
- ❖ Completed 200 hr operation.



DEAP3600 Resurfacer



DEAP3600 Resurfacer




Construction Milestones

- ❖ **Acrylic Vessel completed
November 2013**
- ❖ Installation of inner detector instrumentation through to June 2014
- ❖ AV installed in final location July 2014
- ❖ AV Complete November 2014
- ❖ Steel Shell and Veto PMTs completed April 2015




Construction Milestones

- ❖ Acrylic Vessel completed
November 2013
- ❖ Installation of inner detector
instrumentation through to June
2014
- ❖ AV installed in final location July
2014
- ❖ AV Complete November 2014
- ❖ Steel Shell and Veto PMTs
completed April 2015




Construction Milestones

- ❖ Acrylic Vessel completed
November 2013
- ❖ Installation of inner detector
instrumentation through to June
2014
- ❖ AV installed in final location July
2014
- ❖ AV Complete November 2014
- ❖ Steel Shell and Veto PMTs
completed April 2015



Construction Milestones

- ❖ Acrylic Vessel completed
November 2013
- ❖ Installation of inner detector
instrumentation through to June
2014
- ❖ AV installed in final location July
2014
- ❖ **AV Complete November 2014**
- ❖ Steel Shell and Veto PMTs
completed April 2015




Construction Milestones

- ❖ Acrylic Vessel completed
November 2013
- ❖ Installation of inner detector
instrumentation through to June
2014
- ❖ AV installed in final location July
2014
- ❖ **AV Complete November 2014**
- ❖ Steel Shell and Veto PMTs
completed April 2015




Construction Milestones

- ❖ Acrylic Vessel completed
November 2013
- ❖ Installation of inner detector
instrumentation through to June
2014
- ❖ AV installed in final location July
2014
- ❖ AV Complete November 2014
- ❖ **Steel Shell and Veto PMTs
completed April 2015**



Cryogenics and Process Systems

- ❖ Purification Systems
 - ❖ Delivered and installed
- ❖ Liquid Nitrogen Systems
 - ❖ Storage capable of maintaining AV for 4 days
 - ❖ Commissioned and been operating since June 2014
- ❖ Liquid Argon Storage
 - ❖ Began transfers between surface and SNOLAB March 2015
- ❖ Detector Cooling
 - ❖ Delivered and commissioned June 2014





Calibration Commissioning



- ❖ Successful high voltage ramping of all 255 PMTs
- ❖ Exercised DAQ processing chain
- ❖ Signal injection
- ❖ Light injection system
 - ❖ Acrylic and Aluminium Reflectors and Fibre Optics Systems (AARFS) operated
 - ❖ Laserball before cold data
- ❖ Neutron and Gamma calibration
 - ❖ Deployment hardware complete

Neutron and Gamma Calibration

- ❖ Equator calibration via Cal A, B and E
 - ❖ Provides equal distance calibration set at different ϕ
- ❖ Looped tube Cal F
 - ❖ Provides equal distance calibration set at different θ
 - ❖ Calibration of neck region
- ❖ Calibration tubes and race track served by stepper motor positioning system
- ❖ Calibration via tagged AmBe and ^{22}Na sources





Neutron and Gamma Calibration




AARFS

- ❖ Aluminium coated stubs bonded to 20 light guides around the detector
- ❖ Deliver light via fibres directed at the PMT
- ❖ Light is reflected into the detector
- ❖ 435nm LED and 445nm laser




AARFS




— AARFS Low intensity
— Dark Noise SPE

- ❖ PMT response
- ❖ SPE Calibration
 - ❖ Good dark noise and low light injection agreement
- ❖ PMT Timing
- ❖ Detector optics
 - ❖ Mature light transport models

AARFS




- ❖ PMT response
- ❖ SPE Calibration
 - ❖ Good dark noise and low light injection agreement
- ❖ PMT Timing
- ❖ Detector optics
 - ❖ Mature light transport models



Current and Future

- ❖ TPB vacuum deposition - May
- ❖ Laser ball optical calibration - May
- ❖ Vacuum + TPB data - June
- ❖ Installation of detector cooling coils - July
- ❖ Ultra high purity Argon gas fill and gas data - August onwards

Physics Reach



- ❖ 10⁻⁴⁶ cm² sensitivity at 100 GeV for 3 years physics run
- ❖ First dark matter physics results 2016